L05- 5th FLOOR

PROPOSED TREES

Species	Common Name	Size/Specification	Condition	Quantity (No.)
Amelanchier lamarckii	Juneberry	multistem 250-300 cm high,	RB umbrella form	2
Prunus x subhirtella 'Autumnalis Rosea'	Cherry	160L Pot, 250-300 cm high, multistem	airpot	1

PROPOSED SHRUB PLANTING

Species	Common Name	Size/Specification	Condition	Density No./m2	Area (m2)	Quantity (No.)
Aucuba japonica 'Rozannie' - mass planting	Japanese laurel	5L,40-60cm high	CG	3	5	15
Fasia japonica	Japanese aralia	5L, 60-90cm min.	CG	as shown	n.a.	7
Wisteria floribunda - climber	Japanese Wisteria	5L, 100-120 min.	CG	as shown	n.a.	10

PROPOSED HEDGE PLANTING

Species	Common Name	Size/Specification	Condition	Density No./m	Length/m	Quantity (No.)
Elaeagnus x ebbingei	Oleaster	2L, 60-90cm min.	CG	5	5	25

PROPOSED HERBACEOUS PLANTING

Species	Common Name	Size/Specification	Condition	Density No./m2	Percentage	Area (m2)	Quantity (No.)
Libertia peregrinans	Wandering Chilean iris	2L	CG	5	n.a.	13.6	68
Astelia nervosa 'Westland'	Mountain astelia	5L	CG	as shown	n.a.	n.a.	4
Euphorbia c. wulfennii	Mediterranean spurge	2L	CG	as shown	n.a.	n.a.	3
Phormium 'Platt's Black'	New Zealand flax	5L, 40-50cm min.	CG	as shown	n.a.	n.a.	4

PROPOSED HERBACEOUS PLANTING

Species	Common Name	Size/Specification	Condition	Density No./m2	Percentage	Area (m2)	Quantity (No.)
MIX A						18	
Erysimum 'Bowles Mauve'	Dalmatian Bellflower	6x9 pot	CG	7	40%	7.2	50
Euphorbia amyg. 'Purpurea'	Mrs Robb's bonnet	2L	CG	12	30%	5.4	65
Liriope mucari	Big lily turf	2L	CG	12	10%	1.8	22
Verbascum 'Clementine'	Wallflower	2L	CG	7	20%	3.6	25

Species	Common Name	Size/Specification	Condition	Density No./m2	Percentage	Area (m2)	Quantity (No.)
MIX B						14.1	
Liriope mucari	Big lily turf	2L	CG	12	50%	7.05	85
Blechnum spicant	Hard Fern	2L	CG	7	20%	2.82	20
Asplenium scolopendrium	Hart's Tongue Fern	9cm pot	CG	7	30%	4.2	30
Nectaroscordum siculum	Honey garlic	to BS 3936-9:1968	to BS 3936-9:1968	15	n.a.	14.1	212

Species	Common Name	Size/Specification	Condition	Density No./m2	Percentage	Area (m2)	Quantity (No.)
MIX C						12.4	
Alchemilla mollis	Lady's mantle	2L	CG	7	20%	2.48	17
Anemone x hybrida 'Honorine Jobert'	Japanese anemone	2L	CG	5	30%	3.72	19
Dryopteris erythrosora 'Brillance'	Copper shield fern	2L	CG	9	20%	2.48	22
Euphorbia amyg. var. robbiae	Mrs Robb's bonnet	2L	CG	12	10%	1.24	15
Hakonechloa macra	Japanese forest grass	2L	CG	7	20%	2.48	17

Species	Common Name	Size/Specification	Condition	Density No./m2	Percentage	Area (m2)	Quantity (No.)
MIX D						5.3	
Anemanthele lessoniana	New Zealand wind grass	2L	CG	5	40%	2.12	11
Echinacea 'Magnus'	Purple coneflower	2L	CG	9	20%	1.06	10
Sedum 'Herbstfreude'	Orpine	2L	CG	9	20%	1.06	10
Stachys officinalis 'Hummelo'	Bettony	2L	CG	12	20%	1.06	13

PROPOSED BULB PLANING

Species	Common Name	Size/Specification	Condition	Density No./m2	Area (m2)	Quantity (No.)
Bulb planting mix 'Exotic show'	n.a.	to BS 3936-9:1968	to BS 3936-9:1968	as shown	n.a.	1100

cameo & partners
design studio

Cargo Works - ET 5.07
1-2 Hatfields
Waterloo
London
SE1 9PG
Company Registered No: 8756613.
T : 0203 1760 130
E : info@cameoandpartners.com

rev	details	by	date
09	Issue for planning	EV	20.08.2021
09	Issue for planning	EV	29.07.2021
08	Draft Issue for planning (Updated L01 Entrance)	EV	09.07.2021
07	Issue for planning (Updated with Yellow Brick Building to be retained)	AG	07.06.2021

rev	details	by	date
06	Draft issue for planning (Updated road layout)	EV	15.01.2021
05	Draft issue for planning	EV	08.01.2021
04	Draft issue for planning	EV	18.12.2020
03	Issue for planning	VK	24.06.2020

north

m 0 2 4 6 8 10 12 14 16 18 20
Scale
1:200

DISCLAIMER
1. This drawing is the property of Cameo & Partners Ltd.
2. It must not be copied or reproduced without written consent.
3. Do not scale from this drawing.
4. Check all dimensions on site before setting out.

KEY — PROPOSED SOFT LANDSCAPE

- **Site Boundary**
- **Site Ownership Boundary**
- **Proposed Mature Tree**
  Product: Refer to Planting Schedule
  Supplier: Van den Berk or Similar Approved
  Size/Colour: 35-40cm girth, RB, 2m clear stem.
- **Proposed Shrub Planting**
  Product: Refer to Planting Schedule
  Supplier: TBC
- **Proposed Herbaceous Planting**
  Product: Refer to Planting Schedule
  Supplier: TBC
- **Proposed Climbing Planting**
  Product: Refer to Planting Schedule
  Supplier: TBC
- **Proposed Bulb Planting**
  Scattered arrangement, mixed into the herbaceous planting to provide spring interest.
  Product: Refer to Planting Schedule
  Supplier: Beechill Bulbs

IMPORTANT NOTES:

All plant stock, plant handling and planting to be undertaken in accordance with the following British Standard Specifications and Code of Practice:

BS 3936: 1992 Part 1 Nursery Stock. Specification for Trees and Shrubs.

BS 3936: 1981 Part 10 Nursery Stock. Ground Cover Plants.

BS 4428: 1989 Recommendations for general landscaping operations.

BS 3936-9: 1998 Nursery Stock - Specification for bulbs, corms and tubers.

The Code of Practice for Plant Handling 1985 (Horticultural Trades Association).

Plants not covered by BS 3936 shall be healthy specimens of good shape and balanced branch structure with abundant fibrous roots. Plants are to show vigour of growth within the growing season prior to lifting.

Plant Stock

Plant stock to be supplied in accordance with the size and description specified on the plant schedule. Plant stock shall be healthy, vigorous, and free from pests and diseases and suitably hardened off for the proposed situation of planting, and lifted at a time in accordance with good nursery practice. Stock shall have a well formed fibrous root system and be free from perennial weeds. All Bulbs to be sourced from approved suppliers and will be of good condition, firm, not dried and free of pests, disease and fungus.

Tree Planting

Tenderer's are advised that only well - branched trees with symmetrical crowns and straight stems and leaders will meet with approval of the Landscape Architect. Trees of the same species shall be uniform in size, shape and in good condition.

All tree work shall comply with the recommendations set down in BS. 3998: 1989 Recommendations for tree work. Arising's from tree works shall be carted off site to tip at the Contractors own expense.

Shrub and Herbaceous Perennial Planting

40 litres of compost to be incorporated into the top 200mm of each square meter of topsoil for all ornamental beds.

Failures of Planting

Plants that have failed to thrive will be replaced with equivalent plants. Replacements to match size of adjacent or nearby plants of same species or match original specification, whichever is the greater.

Mulching

All soft landscape areas to be mulched with a 50 mm layer of ornamental 'TMA Bark Supplies' or similar grade bark mulch when planting work has been completed.

THE PLANT LIST MUST NOT BE CHANGED WITHOUT NOTICING THE LANDSCAPE ARCHITECTS. ANY CHANGES MUST BE CONFIRMED BY CAMEO AND PARTNERS LTD.

Project
Tedcastle Residential Development

Drawing
Terrace Landscape Planting Plan - L05

Scale	Date	Checked By	Drawn By
1:200@A1	12.06.2020	MM	VK

Drawing No.
C0101 L305

Revision
09

Purpose of Issue.
P
D = design information / P = planning / T = tender / C = construction / B = as built

Drawing sheet size - A1

© Cameo & Partners